

STATE OF COLORADO
Cover Sheet for Building Specifications, Third Party
Reviews, and QA Manuals

Name of Manufacturer: Champion Homes (dba Highland Manufacturing) Plant I.D. Number: 166

Manufacturer Address: 1660 Rowe Avenue, Worthington, MN 56187

Manufacturer Contact Name and Contact Number: Mark Lively (Engineering Manager) 507-295-0880

Manufacturer Contact Email address: mlively@championhomes.com

Third Party Inspection Agency (if not CDOH): _____

Third Party Plan Review Agency (if applicable): PFS



Third Party Plan Review Approval Name/Number (if applicable): _____

Factory Type: FB FBNR Tiny Homes HUD Homes

Document Type: New Plan Revision Renewal

Model Name/No.:

MANUFACTURER CERTIFIES that only approved equipment and materials will be used and the installations shall be made in accordance with approved plans and applicable codes and provisions of the Colorado Division of Housing. Manufacturer agrees to in-plant inspection of units manufactured under the above plan approval. Application shall be made for and insignia affixed to each factory built unit that is subject to Colorado statutes and which is manufactured or is to be sold, offered for sale, or occupied in the state of Colorado.

Sq. Footage Finished: 1980 Sq. Footage Unfinished: 300		State of Colorado Division of Housing Apr 12 2024
CDOH Approval Stamp		  APPROVED PLANS Subject to field inspection OC INSPECTION REQUIRED
Expiration Date 1/1/25	CDOH Plan Approval Number R-00060740C	



Model Number: 290-KBM-3266S33005 (Tarczali)

Residential (IRC) & Tiny Home Plan Submission Checklist

*A full plan set submission to the Colorado Division of Housing includes the following:
(Electronic Plan Submissions Only)*

Submitted	Document Type
<input checked="" type="checkbox"/>	<ul style="list-style-type: none">Plan Review Payment through Salesforce
	Plan Set Package
	Architectural Plan Set
X	<ul style="list-style-type: none">Initialed and signed copy of the Plan Submission Checklist confirming applicable documents have been included in the plan package.
X	<ul style="list-style-type: none">Index of submitted plan package<ul style="list-style-type: none">Can be a separate document or clearly denoted on cover page
X	<ul style="list-style-type: none">Site location where structure is to be installed, and Local Authority Having Jurisdiction, or designate the structure as lot model with design loads that are specific for the area the home can be installed, and a minimum setback distance noted for fire separation requirements. If site location is known, a site plan, set back distances to lot lines or other structures, and local AHJ Wildfire Mitigation area requirements (if any) are required to determine fire separation requirements for structure. If structure is to be set in a location where there is no local authority having jurisdiction or lot model, at a minimum, the design loads must comply with 8 CCR 1302-14, Rule 2.2.1.
X	<ul style="list-style-type: none">Code Analysis<ul style="list-style-type: none">Design CodesWind, and Snow Loads (must meet local AHJ and CDOH minimums)Seismic and Wind Exposure categoryType of Fire suppression system if applicable (factory installed or on site)<ul style="list-style-type: none">If location is known, clearly denote on code analysis if the jurisdiction require a fire suppression system. If one is required and any of the installation is to be in-plant, then it must comply with Colorado Division of Fire Safety & Control Rules (8 CCR 1507-11) & a CORI shall accompany the units throughout the process.
X	<ul style="list-style-type: none">List of items to be completed on site<ul style="list-style-type: none">OC Form included that complies with 8 CCR 1302-14, Rules 1.19, 4.17.1.1, and C.R.S. 24-32-3311(1)(a.7)
X	<ul style="list-style-type: none">Architectural plans with applicable details<ul style="list-style-type: none">Floor Plan for Each LevelRoom Use SpecificationWindow and Door SchedulesElevationsSection Drawings (Full and at Stairs)



NA	<ul style="list-style-type: none">• Fire Rated Assembly Details (If applicable)<ul style="list-style-type: none">○ Assemblies not exempt in section R302 to be fire rated or other sections in the code, need to have details showing compliance with section R302 of the IRC for separation of dwellings, fire separation distances, and/or floors. Must comply with the testing standards of either ASTM E119 or UL263 or section 703.3 of the IBC.○ If section 722 of the IBC has been opted for compliance, the design must be approved through a Colorado Registered Fire Protection engineer.
	Structural Framing Plans
X	<ul style="list-style-type: none">• Components<ul style="list-style-type: none">○ Floor Assemblies○ Wall Assemblies○ Roof Assemblies○ Ceiling Assemblies○ Headers, Beams and Columns○ Proposed Foundation○ Braced Wall line details, and tie down equipment with locations that are not specifically addressed in approved installation manual.○ Construction components exceeding section R301 of the IRC, shall have plans stamped by a Colorado Registered Design Professional.
	MEP Plan Sheets
X	<ul style="list-style-type: none">• Mechanical System Plans<ul style="list-style-type: none">○ Exhaust Locations○ Whole home ventilation systems
X	<ul style="list-style-type: none">• Electrical System Plans<ul style="list-style-type: none">○ Fixtures, load calculations, panel/circuit schedule with breaker and wire sizing, symbols legend, etc.
X	<ul style="list-style-type: none">• Plumbing System Plans<ul style="list-style-type: none">○ Service water piping with piping location, insulation and size○ Fixture types and locations○ Isometric for DWV, indicate pipe sizes
NA	<ul style="list-style-type: none">• Gas System Plans<ul style="list-style-type: none">○ Gas Isometric with distances and BTU ratings of appliances it serves○ Piping material and sizes, service pressure ratings
	Spec Set Package
X	<ul style="list-style-type: none">• Spec Cover Sheet
X	<ul style="list-style-type: none">• Copy of the “OC” Inspection letter denoting the “OC” inspection items listed on the submitted plans. Information from the site address on the first page to the “factory authorized representative” portion to the date must be filled in by the factory, except for the CDOH P/A NO (DOH assigned).
X	<ul style="list-style-type: none">• Engineered/Certified Component Details<ul style="list-style-type: none">○ Engineered and stamped truss details by a State of Colorado professional designed per TPI 1 - 2014 per IRC 2018. Include correct loading and wind speed & exposure, etc.○ Tiny Home chassis must be engineer approved or certified by NHTSA
	<ul style="list-style-type: none">• Energy Compliance



COLORADO

Department of Local Affairs

Division of Housing

JULY 2023

X	<ul style="list-style-type: none">○ REScheck (<i>signed</i>)<ul style="list-style-type: none">▪ Use appropriate version 2015 (or 2012, 2009 based on local adoption)▪ Use the Colorado city where the building will be installed (If site location is not a selection on REScheck, list exact location on Construction Site information box)• If a REScheck is omitted and the prescriptive method is opted for use, please clearly denote on plans a table showing the information depicted in the IECC, Section R103.2 and applicable information per 8 CCR 1302-14, Rule 2.7
X	<ul style="list-style-type: none">• HVAC System Plans<ul style="list-style-type: none">○ Load calculations for equipment sizing (Manual J)○ Equipment size listed and meets or exceeds load calculation with deration (Manual S)○ Supply and return air sizing and plans (Manual D)○ Site information must match information provided on the REScheck

The Colorado Division of Housing plan review does not begin until the entire plan submission is received.

Applicant must sign below acknowledging submittal checklist has been read and all applicable documents have been submitted for review and any changes to plans require plans to be resubmitted for review, and approved by DOH before construction. All DOH plans are subject to field inspection. Additional information not included in this general list may be requested by DOH plan reviewers to complete review.

X Mark Lively Date: 3/22/2024

For additional plan review requirements, questions, or concerns, please reach out to our staff at:

FB/FBNR
manufactured.plans@state.co.us
Tiny Homes
dola_tinyhomes@state.co.us





“OC” (On-site Construction) Form

Please read below before signing form.

Please See Attached Document at bottom of form for Specific plan and Manufacturer information.

To: The Local Authority Having Jurisdiction (LAHJ) or other DOH approved third party inspection agency.

By signing this form, you confirm that you have received and reviewed this form, and acknowledge that the identified components below are required to complete the construction of this modular structure onsite within your jurisdiction.

Building Official Responsibility

Please check the box labeled “Accept” and initial to confirm that you will take responsibility for inspections of the “OC” Inspection Items on behalf of the DOH. You also acknowledge that it will be done to the DOH approved plans.

If you would like to defer inspection of the “OC” Inspection Items back to the DOH, please check the box labeled “Defer Inspection”.

ATTENTION

“On-site Construction” or “OC” means on-site construction or modification of the factory-built structure that directly relates to the durability, quality, and safety; that is completed at the installation “site” as defined by section 24-32-3302(33), C.R.S.; using components not installed at the manufacturer’s location; and to complete the compliance of that structure as reflected in the Division of Housing approved plans. These items do not include the component(s) required for setting and securing the structure for its installation.

Fire Safety Official Responsibility (if applicable)

The DOH defers the requirement of any fire protection system for all modular IBC (Section 901.2) and IRC (Section R313) structures as follows:

An automatic fire sprinkler system shall be installed in buildings (IBC) OR one and two family dwellings and townhouses (IRC) OR Tiny homes as required by the local jurisdiction where the structure or home will be set. Final tests required by this Section shall be approved by a certified inspector. The inspector must be either an employee of the fire department having jurisdiction or another qualified individual with prior approval of the Colorado Division of Fire Prevention & Control.

Wild Fire mitigation requirements will be deferred for (IBC) OR one and two family dwellings and townhouses (IRC) OR Tiny homes as required by the local jurisdiction where the structure or home will be set. Final inspections required by locals shall be approved by a certified inspector. The inspector must be either an employee of the fire department having jurisdiction or another qualified individual with prior approval of the Colorado Division of Fire Prevention & Control.





JULY 2023

Please confirm if the LAHJ requires a fire protection system and/or wild fire mitigation for this modular structure. If so, please indicate if the inspection will be completed by a fire department (identify which one) or whether it will be completed by the Colorado Division of Fire Prevention & Control.

Manufacturer Responsibility

The registered manufacturer is responsible for manufacturing a structure that is compliant with our Administrative Rules (CCR 1302-14). If items in the factory have not been completed, only to be completed in the field, you are still responsible for ensuring they have been completed for compliance. Please sign below that you have received this letter and acknowledge the items listed are to complete compliance of the structure, and items are to be inspected and passed for compliance in order to meet Rule 1.13.1 and section 24-32-3311(4), Colorado Revised Statutes (C.R.S.).

ATTENTION

A DOH issued insignia (silver for residential or blue for nonresidential or pink for tiny homes or black for multi-family) certifying its construction cannot be affixed to the structure until all "OC" items are completed on site and pass inspection. The same applies to modular structures manufactured by a certified manufacturer.

Acknowledge Receipt and Understanding

Normal permits and fees for these site work inspections are to be per the local jurisdiction.

State approved plans for Factory-Built Construction may be obtained from the Builder/Manufacturer.

A copy of this completed form is included with the DOH approved plans and must be included with the installation instructions and shipped with the unit. If the completed form has been damaged or lost during shipping, the manufacturer or its representative can obtain a copy from the DOH.

Before any inspection is scheduled at the on-site location or Installation Authorization (required for modular homes and multi-family structures) is issued by the DOH, this form will be required to be signed and dated by the Building Official, or Approved Third Party Agent, or Fire Safety Official (if applicable), and submitted to the DOH.

The DOH approved OC form will be included with the approved spec file, with the DOH Plan Reviewer signature below and their plan approval stamp on the page(s) with the OC listed items to be completed at the site location. That approved OC form should be submitted to the appropriate parties described in this form and submitted back to the DOH before any inspection is scheduled at the onsite location or Installation Authorization (required for modular homes and multi-family structures) is issued.

DOH Plan Reviewer Name _____

DOH Plan Reviewer Signature _____

Date Approved _____

Contact email: _____





JULY 2023

Building Department Representative Printed Name _____

Building Department Representative Signature _____

Title _____

Date _____

☐

Accept

☐

Defer Inspection

Contact email: _____

If applicable:

Fire Safety Official Printed Name _____

Fire Safety Official Signature _____ Date _____

Contact email: _____

Is a fire protection system required? (check one) Required Not Required

If required, the inspection is to be performed by (check one):

_____ Fire Department: (NAME) _____

OR

_____ Colorado Division of Fire Prevention & Control

Manufacturer's Authorized Quality Assurance Representative

Printed Name Rebecca Santiago

Manufacturer's Authorized Quality Assurance Representative

Signature *Rebecca Santiago* Date 03/14/2024

Contact email: rsantiago@championhomes.com

If the inspection has been deferred and the manufacturer elects to utilize an Approved Third Party Agency to inspect the "OC" items on behalf of DOH, please sign and date below.

Approved Third Party Agent Printed Name _____

Approved Third Party Agent Signature _____ Date _____

Contact email: _____





JULY 2023

Verify Inspection(s) Completed

Once you have completed all of your assigned inspections identified in this form and they have passed for compliance, please sign and date below.

Building Department Representative Printed Name _____

Building Department Representative Signature _____

Date _____

Contact email: _____

Or

Approved Third Party Agent Printed Name _____

Approved Third Party Agent Signature _____ Date _____

Contact email: _____

Fire Protection Systems (if applicable)

Fire Safety Official Printed Name _____

Fire Safety Official Signature _____ Date _____

Contact email: _____

Please direct questions to manufactured.plans@state.co.us





JULY 2023

The following is based on information provided to the Division of Housing (DOH) and may be modified based on the actual findings of the field inspection.

DATE: 3/22/2024

MANUFACTURER: Highland Manufacturing

ID NO.: 166

CONTACT: Mark Lively

PHONE NO.: 507-295-0880

MODEL NO.: 290-KBM-3266S33005 (Tarczali)

DOH P/A NO.:

INSPECTION REQUIREMENTS: Check on site:

“OC” Inspection Items

Foundation construction, all earth work, & below grade insulation per ResCheck.
Extension of gas vents and/or chimneys to the exterior.
Furnace stack and cap installation.
Drain vent (VTR) installation of extensions and couplers.
Siding installation for the ends of the house.
Vented ridge cap installation.



Champion Home Builders, Inc.
DBA Highland Manufacturing
Model: 290-KBM-3266S33005

Index:

Specifications package

- 1 Application
- 2 Site information
- 3 Heating/Cooling Calculations and Layout (AMS Manual J)
- 4 Truss Details
- 5 Thermal Calculations (ResCheck)
- 6 Deration Calculations
- 7 Electrical Load Calculations
- 8 Shear Wall Calculations
- 9 Porch Ridge Beam Calculations
- 10 Porch Side Wall Header Calculations

Colorado

Requirements from the state:

Site location where structure is to be installed, and Local Authority Having Jurisdiction, or designating the structure as lot model with design loads that are specific for the area the structure is to be installed, and a minimum setback distance noted for fire separation requirements. If site has adjacent structures, a site plan and set back distances to lot lines or other structures is required to determine fire separation requirements for structure. If structure is to be set in a location where there is no local authority having jurisdiction or lot model, at a minimum, the design loads must comply with 8 CCR 102.14, Rule 2.1.

Site information needed to get approvals:

Full name of owner(s): Thomas Tarczali/Christi

Street Address: 820 S. St. Vrain Ave.

City & Zip: Estes Park, CO 80517

Phone: 970-231-4218 Email: thomastarczali@yahoo.com

Parcel#: _____

Local Authority Having Jurisdiction (LAHJ): Town of Estes Park

Wind Speed: 165 Snow Load: 100 (Roof) (Ground)

Site Set Back requirements:

1. Front 10'

2. Back 10'

3. Sides 10'

Attach a Site Plan (preferable a GIS print out) with dimensions and/or scaling.

(sent 3/6/24)


boundaries on the zoning districts shown hereon. These boundaries follow property boundaries as delineated on this map.

This map shall not be used to:

Establish specific legal lots of record, or individual parcel boundaries; or

Establish property descriptions for legal conveyance of parcels of land.

Individual property boundaries are subject to frequent change, and recent changes may not be reflected on this map. Larimer County and the Town of Estes Park cannot anticipate and do not assume responsibility or liability for subsequent, secondary use of this map. No representation or warranty is made as to the completeness or accuracy of this map for any use other than the intended use of identifying zoning district boundaries.



Tarczali
820 S. St. Vrain Ave.
Estes Park, CO
80517

Town of Estes
Larimer County



Legend

Ground Snow Load Contours	Basic Wind Speed (3s)	Road System
1000 ft Index Contours	Addresses	Lakes and Ponds
Under 7000 ft = 30 psf	Subdivisions	Major Rivers and Streams
7000-7999 ft = 40 psf	Tax Parcels	Rivers and Streams
8000-8999 ft = 50 psf	Platted Lots	County Boundary

Notes

0.0 0 0.0 Miles

Date Prepared: 8/15/2023 6:03:58 AM

Scale
1: 600



This map was created by Larimer County GIS using data from multiple sources for informal purposes only. This map may not reflect recent updates prior to the date of printing. Larimer County makes no warranty or guarantee concerning the completeness, accuracy, or reliability of the content represented.



Manual S Compliance Report

Entire House

AMS Of Indiana, Inc.

Job: KBM-3266 S3 3005-TARC...
Date: 3/6/24
By: AMS of Indiana, Inc.

3933 East Jackson Blvd., Elkhart, IN 46516

Project Information

For: CHAMPION HOME BUILDERS, KBM-3266 S3 3005-TARCZALI

Cooling Equipment

Design Conditions

Outdoor design DB:	79.0°F	Sensible gain:	10875	Btuh	Entering coil DB:	75.5°F
Outdoor design WB:	58.0°F	Latent gain:	0	Btuh	Entering coil WB:	60.9°F
Indoor design DB:	75.0°F	Total gain:	10875	Btuh		
Indoor RH:	50%	Estimated airflow:	644	cfm		

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Split AC		
Manufacturer:	Generic	Model:	SEER 14.0
Actual airflow:	644	cfm	
Sensible capacity:	9135	Btuh	84% of load
Latent capacity:	3915	Btuh	0% of load
Total capacity:	13050	Btuh	120% of load SHR: 70%

Heating Equipment

Design Conditions

Outdoor design DB:	-7.0°F	Heat loss:	32525	Btuh	Entering coil DB:	60.8°F
Indoor design DB:	70.0°F					

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Gas furnace		
Manufacturer:	Generic	Model:	AFUE 95
Actual airflow:	644	cfm	
Output capacity:	39330	Btuh	121% of load
			Temp. rise: 0 °F

Meets all requirements of ACCA Manual S.



Load Short Form
Entire House
AMS Of Indiana, Inc.

Job: KBM-3266 S3 3005-TARC...
Date: 3/6/24
By: AMS of Indiana, Inc.

3933 East Jackson Blvd., Elkhart, IN 46516

Project Information

For: CHAMPION HOME BUILDERS, KBM-3266 S3 3005-TARCZALI

Design Information

	Htg	Clg	Infiltration	
Outside db (°F)	-7	79	Method	Simplified
Inside db (°F)	70	75	Construction quality	Average
Design TD (°F)	77	4	Fireplaces	0
Daily range	-	M		
Inside humidity (%)	50	50		
Moisture difference (gr/lb)	69	-24		

HEATING EQUIPMENT

Make	Generic
Trade	
Model	AFUE 95
AHRI ref	
Efficiency	95 AFUE
Heating input	60000 Btuh
Heating output	39330 Btuh
Temperature rise	74 °F
Actual air flow	644 cfm
Air flow factor	0.023 cfm/Btuh
Static pressure	0.50 in H2O
Space thermostat	

COOLING EQUIPMENT

Make	Generic
Trade	
Cond	SEER 14.0
Coil	
AHRI ref	
Efficiency	12.2 EER, 14 SEER
Sensible cooling	9135 Btuh
Latent cooling	3915 Btuh
Total cooling	13050 Btuh
Actual air flow	644 cfm
Air flow factor	0.061 cfm/Btuh
Static pressure	0.50 in H2O
Load sensible heat ratio	1.00

ROOM NAME	Area (ft²)	Htg load (Btuh)	Clg load (Btuh)	Htg AVF (cfm)	Clg AVF (cfm)
DRKTLR	773	9684	5674	225	344
U	116	1137	166	26	10
BA2	61	506	64	12	4
C1	58	483	61	11	4
B1	244	3241	1508	75	91
BA1	150	2285	738	53	45
B2	173	1339	914	31	55
B3	173	1355	922	31	56
ENTRY	80	1201	541	28	33
BA3	37	84	39	2	2
PTY	33	0	0	0	0
H	85	0	0	0	0
CRWL	1980	6420	0	149	0

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Right-Suite® Universal 2023 23.0.05 RSU02009

...MN 290KBM-3266 S3 3005-TARCZALI(FIBG-PER).rup Calc = MJ8 House faces: W

2024-Mar-06 12:04:32

Page 1

Entire House	3960	27735	10627	644	644
Other equip loads		4790	249		
Equip. @ 0.84 RSM			9135		
Latent cooling			0		
TOTALS	3960	32525	9135	644	644

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Right-Suite® Universal 2023 23.0.05 RSU02009

2024-Mar-06 12:04:32

Page 2

...-MN 290KBM-3266 S3 3005-TARCZALI(FIBG-PER).rup Calc = MJ8 House faces: W

Project Information

For: CHAMPION HOME BUILDERS, KBM-3266 S3 3005-TARCZALI

Design Conditions

Location:

Boulder 14 W, CO, US
Elevation: **7761** ft
Latitude: 40°N

Outdoor:

Dry bulb (°F)
Daily range (°F)
Wet bulb (°F)
Wind speed (mph)

Heating

-7
-
-
15.0

Cooling

79
23 (M)
58
7.5

Indoor:

Indoor temperature (°F)
Design TD (°F)
Relative humidity (%)
Moisture difference (gr/lb)

Heating

70
77
50
69.3

Cooling

75
4
50
-24.0


Infiltration:

Method
Construction quality
Fireplaces

Simplified
Average
0


Heating

Component	Btuh/ft²	Btuh	% of load
Walls	4.8	10552	32.4
Glazing	20.0	4188	12.9
Doors	19.3	1617	5.0
Ceilings	1.5	3049	9.4
Floors	1.5	3049	9.4
Infiltration	3.1	5280	16.2
Ducts		0	0
Piping		0	0
Humidification		0	0
Ventilation		4790	14.7
Adjustments		0	0
Total		32525	100.0



Cooling

Component	Btuh/ft²	Btuh	% of load
Walls	0.1	275	2.5
Glazing	27.9	5836	53.7
Doors	3.5	297	2.7
Ceilings	0.8	1491	13.7
Floors	0	0	0
Infiltration	0.1	147	1.4
Ducts		0	0
Ventilation		249	2.3
Internal gains		2580	23.7
Blower		0	0
Adjustments		0	0
Total		10875	100.0



Latent Cooling Load = 0 Btuh

Overall U-value = 0.045 Btuh/ft²-°F, Window / Floor Area = 5.3 %

Data entries checked.

Bold/italic values have been manually overridden

Project Information

For: CHAMPION HOME BUILDERS, KBM-3266 S3 3005-TARCZALI

Design Conditions

Location:		Indoor:		Heating	Cooling
Boulder 14 W, CO, US		Indoor temperature (°F)		70	75
Elevation: 7761 ft		Design TD (°F)		77	4
Latitude: 40°N		Relative humidity (%)		50	50
		Moisture difference (gr/lb)		69.3	-24.0
Outdoor:	Heating	Cooling	Infiltration:		
Dry bulb (°F)	-7	79	Method	Simplified	
Daily range (°F)	-	23 (M)	Construction quality	Average	
Wet bulb (°F)	-	58	Fireplaces	0	
Wind speed (mph)	15.0	7.5			

Construction descriptions

	Or	Area ft ²	U-value Btuh/ft ² ·°F	Insul R ft ² ·°F/Btuh	Htg HTM Btuh/ft ²	Loss Btuh	Clg HTM Btuh/ft ²	Gain Btuh
Walls 12F-0sw: Fm wall, vnl ext, 3/8" wood shth, r-21 cav ins, 1/2" gypsum board int fnsh, 2"x6" wood frm, 16" o.c. stud	ne	511	0.065	21.0	5.00	2559	0.19	98
	se	270	0.065	21.0	5.00	1351	0.19	52
	sw	471	0.065	21.0	5.00	2355	0.19	90
	nw	183	0.065	21.0	5.00	916	0.19	35
	all	1435	0.065	21.0	5.00	7181	0.19	275
15B15-0wc-4: Bg wall, light dry soil, 2"x4" wood int frm, concrete wall, r-15 cav ins, 8" thk	ne	264	0.057	15.0	4.39	1159	0	0
	se	120	0.057	15.0	4.39	527	0	0
	sw	264	0.057	15.0	4.39	1159	0	0
	nw	120	0.057	15.0	4.39	527	0	0
	all	768	0.057	15.0	4.39	3371	0	0

Partitions

(none)

Windows

2 glazing, clr low-e outr, argon gas, vnl frm mat, clr innr, clr strm, 1/4" gap, 1/8" thk; 2 glazing, clr low-e outr, argon gas, vnl frm mat, clr innr, clr strm, 1/4" gap, 1/8" thk; NFRC rated (SHGC=0.30); 6.67 ft head ht	ne	62	0.260	0	20.0	1235	19.7	1212
	sw	103	0.260	0	20.0	2052	24.7	2532
	nw	45	0.260	0	20.0	901	19.7	885
	all	209	0.260	0	20.0	4188	22.1	4629

Doors

Door, wd sc type	ne	21	0.170	0	13.1	275	2.41	51
	sw	21	0.170	0	13.1	275	2.41	51
	nw	42	0.330	0	25.4	1067	4.67	196
	all	84	0.330	0	19.3	1617	3.54	297

Ceilings

16B-50ad: Attic ceiling, asphalt shingles roof mat, r-50 ceil ins, 1/2" gypsum board int fnsh	1980	0.020	50.0	1.54	3049	0.75	1491
---	------	-------	------	------	------	------	------

Floors

21A-32t: Bg floor, light dry soil, 4' depth	1980	0.020	0	1.54	3049	0	0
---	------	-------	---	------	------	---	---

Bold/italic values have been manually overridden

Project Information

For: CHAMPION HOME BUILDERS, KBM-3266 S3 3005-TARCZALI

Notes: FURNACE DERATED FOR ELEVATION

Design Information

Weather: Boulder 14 W, CO, US

Winter Design Conditions

Outside db	-7 °F
Inside db	70 °F
Design TD	77 °F

Summer Design Conditions

Outside db	79 °F
Inside db	75 °F
Design TD	4 °F
Daily range	M
Relative humidity	50 %
Moisture difference	-24 gr/lb

Heating Summary

Structure	27735 Btuh
Ducts	0 Btuh
Central vent (75 cfm)	4790 Btuh
Outside air	
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	32525 Btuh

Sensible Cooling Equipment Load Sizing

Structure	10627 Btuh
Ducts	0 Btuh
Central vent (75 cfm)	249 Btuh
Outside air	
Blower	0 Btuh
Use manufacturer's data	n
Rate/swing multiplier	0.84
Equipment sensible load	9135 Btuh

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

Latent Cooling Equipment Load Sizing

Structure	655 Btuh
Ducts	0 Btuh
Central vent (75 cfm)	-922 Btuh
Outside air	
Equipment latent load	0 Btuh

	Heating	Cooling
Area (ft²)	3960	3960
Volume (ft³)	17820	17820
Air changes/hour	0.28	0.15
Equiv. AVF (cfm)	83	45

Equipment Total Load (Sen+Lat)	9135 Btuh
Req. total capacity at 0.70 SHR	1.1 ton

Heating Equipment Summary

Make	Generic
Trade	
Model	AFUE 95
AHRI ref	
Efficiency	95 AFUE
Heating input	60000 Btuh
Heating output	39330 Btuh
Temperature rise	74 °F
Actual air flow	644 cfm
Air flow factor	0.023 cfm/Btuh
Static pressure	0.50 in H2O
Space thermostat	

Cooling Equipment Summary

Make	Generic
Trade	
Cond	SEER 14.0
Coil	
AHRI ref	
Efficiency	12.2 EER, 14 SEER
Sensible cooling	9135 Btuh
Latent cooling	3915 Btuh
Total cooling	13050 Btuh
Actual air flow	644 cfm
Air flow factor	0.061 cfm/Btuh
Static pressure	0.50 in H2O
Load sensible heat ratio	1.00

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

3933 East Jackson Blvd., Elkhart, IN 46516

1 Name of Room				C1				B1				
2 Running Feet of Exposed Wall				5.3 ft				31.3 ft				
3 Ceiling Ht (Ft) and Gross Wall Area (SqFt)				9.0 ft 292.5 ft²				9.0 ft 562.5 ft²				
4 Room Dimensions (Ft) and Floor Plan Area (SqFt)				5.3 x 11.0 ft 57.8 ft²				16.3 x 15.0 ft 243.8 ft²				
5 Ceiling Slope (Deg.) and Gross Ceiling Area (SqFt)				0° 57.8 ft²				0° 243.8 ft²				
Type of Exposure	Const. Number	Panel Faces	HTM		Area or Length	Btuh			Area or Length	Btuh		
			Htg.	Clg.		Heating	S-Clg	L-Clg		Heating	S-Clg	L-Clg
6 Wall	12F-0sw	ne	5.00	0.19	47	236	9		146	536	21	
Glaz	2 glazing, dr low-e	ne	20.02	19.66	0	0	0		39	784	770	
Door	Door, wd sc type	ne	13.09	2.41	0	0	0		0	0	0	
11 Wall	15B15-0wc-4	ne	4.39	0.00	0	0	0		0	0	0	
Wall	12F-0sw	se	5.00	0.19	0	0	0		135	676	26	
Wall	15B15-0wc-4	se	4.39	0.00	0	0	0		0	0	0	
Wall	12F-0sw	sw	5.00	0.19	0	0	0		0	0	0	
Glaz	2 glazing, dr low-e	sw	20.02	24.70	0	0	0		0	0	0	
Door	Door, wd sc type	sw	13.09	2.41	0	0	0		0	0	0	
Wall	15B15-0wc-4	sw	4.39	0.00	0	0	0		0	0	0	
Wall	12F-0sw	nw	5.00	0.19	0	0	0		0	0	0	
Glaz	2 glazing, dr low-e	nw	20.02	19.66	0	0	0		0	0	0	
Door	Door, wd sc type	nw	25.41	4.67	0	0	0		0	0	0	
Wall	15B15-0wc-4	nw	4.39	0.00	0	0	0		0	0	0	
Ceil	16B-50ad	-	1.54	0.75	58	89	43		244	375	184	
Flor	21A-32t	-	1.54	0.00	0	0	0		0	0	0	
12 Infiltration	Heating Load (Btuh)		Effect ACH		0.28	WAR	144		WAR	859		
	Sensible Load (Btuh)				0.15	0.03		4	0.16		24	
	Latent Load (Btuh)											
13 Internal	a Occupants at 230 and 200 Btuh				0		0	0	2		460	400
	b Scenario number						0				0	
	c Default Adjustments											
	d Custom Appliances						0	0			0	0
	e Plants							0				0
14 Subtotals	Sum lines 6 through 12					483	61			3241	1508	
15 Duct Loads	EHLF & ESGF		0	0		0	0			0	0	
	ELG							0				0
16 Ventilation Loads	Vent Cfm	75	E Cfm	75								
17 Winter Humidification Load	Gal/Day			0								
18 Piping Load												
19 Blower Heat												
20 AED Excursion & Latent Moisture Migration Load							-2				19	
21 Total Load	Sum lines 13 through 19					483	61			3241	1508	

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

3933 East Jackson Blvd., Elkhart, IN 46516

1 Name of Room				BA1 25.0 ft					B2 11.5 ft				
2 Running Feet of Exposed Wall				9.0 ft 450.0 ft²					9.0 ft 477.0 ft²				
3 Ceiling Ht (Ft) and Gross Wall Area (SqFt)				10.0 x 15.0 ft 150.0 ft²					11.5 x 15.0 ft 172.5 ft²				
4 Room Dimensions (Ft) and Floor Plan Area (SqFt)				0 ° 150.0 ft²					0 ° 172.5 ft²				
5 Ceiling Slope (Deg.) and Gross Ceiling Area (SqFt)													
Type of Exposure	Const. Number	Panel Faces	HTM		Area or Length	Btuh			Area or Length	Btuh			
			Htg.	Clg.		Heating	S-Clg	L-Clg		Heating	S-Clg	L-Clg	
6 Wall	12F-0sw	ne	5.00	0.19	0	0	0		0	0	0		
Glaz	2 glazing, dr low-e	ne	20.02	19.66	0	0	0		0	0	0		
Door	Door, wd sc type	ne	13.09	2.41	0	0	0		0	0	0		
11 Wall	15B15-0wc-4	ne	4.39	0.00	0	0	0		0	0	0		
Wall	12F-0sw	se	5.00	0.19	135	676	26		0	0	0		
Wall	15B15-0wc-4	se	4.39	0.00	0	0	0		0	0	0		
Wall	12F-0sw	sw	5.00	0.19	90	370	14		104	443	17		
Glaz	2 glazing, dr low-e	sw	20.02	24.70	16	320	395		15	300	371		
Door	Door, wd sc type	sw	13.09	2.41	0	0	0		0	0	0		
Wall	15B15-0wc-4	sw	4.39	0.00	0	0	0		0	0	0		
Wall	12F-0sw	nw	5.00	0.19	0	0	0		0	0	0		
Glaz	2 glazing, dr low-e	nw	20.02	19.66	0	0	0		0	0	0		
Door	Door, wd sc type	nw	25.41	4.67	0	0	0		0	0	0		
Wall	15B15-0wc-4	nw	4.39	0.00	0	0	0		0	0	0		
Ceil	16B-50ad	-	1.54	0.75	150	231	113		173	266	130		
Flor	21A-32t	-	1.54	0.00	0	0	0		0	0	0		
12 Infiltration	Heating Load (Btuh)		Effect ACH		0.28	WAR	687		WAR	316			
	Sensible Load (Btuh)				0.15	0.13		19	0.06		9		
	Latent Load (Btuh)												
13 Internal	a Occupants at 230 and 200 Btuh				0		0	0	1		230	200	
	b Scenario number						0				0		
	c Default Adjustments							0			0	0	
	d Custom Appliances							0			0	0	
	e Plants							0			0	0	
14 Subtotals	Sum lines 6 through 12					2285	738			1339	914		
15 Duct Loads	EHLF & ESGF		0	0		0	0			0	0		
	ELG							0			0		
16 Ventilation Loads	Vent Cfm	75	E Cfm	75									
17 Winter Humidification Load	Gal/Day			0									
18 Piping Load													
19 Blower Heat													
20 AED Excursion & Latent Moisture Migration Load							171				152		
21 Total Load	Sum lines 13 through 19					2285	738			1339	914		

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

3933 East Jackson Blvd., Elkhart, IN 46516

[illegible]

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

3933 East Jackson Blvd., Elkhart, IN 46516

1 Name of Room				H 0 ft				CRWL 192.0 ft					
2 Running Feet of Exposed Wall				9.0 ft				454.5 ft²					
3 Ceiling Ht (Ft) and Gross Wall Area (SqFt)				21.3 x 4.0 ft				85.0 ft²					
4 Room Dimensions (Ft) and Floor Plan Area (SqFt)				0 °				85.0 ft²					
5 Ceiling Slope (Deg.) and Gross Ceiling Area (SqFt)				0 °				1980.0 ft²					
Type of Exposure	Const. Number	Panel Faces	HTM		Area or Length	Btuh			Area or Length	Btuh			
			Htg.	Clg.		Heating	S-Clg	L-Clg		Heating	S-Clg	L-Clg	
6 Wall	12F-0sw	ne	5.00	0.19	0	0	0	0	0	0	0	0	
Glaz	2 glazing, dr low-e	ne	20.02	19.66	0	0	0	0	0	0	0	0	
Door	Door, wd sc type	ne	13.09	2.41	0	0	0	0	0	0	0	0	
11 Wall	15B15-0wc-4	ne	4.39	0.00	0	0	0	0	264	1159	0	0	
Wall	12F-0sw	se	5.00	0.19	0	0	0	0	0	0	0	0	
Wall	15B15-0wc-4	se	4.39	0.00	0	0	0	0	120	527	0	0	
Wall	12F-0sw	sw	5.00	0.19	0	0	0	0	0	0	0	0	
Glaz	2 glazing, dr low-e	sw	20.02	24.70	0	0	0	0	0	0	0	0	
Door	Door, wd sc type	sw	13.09	2.41	0	0	0	0	0	0	0	0	
Wall	15B15-0wc-4	sw	4.39	0.00	0	0	0	0	264	1159	0	0	
Wall	12F-0sw	nw	5.00	0.19	0	0	0	0	0	0	0	0	
Glaz	2 glazing, dr low-e	nw	20.02	19.66	0	0	0	0	0	0	0	0	
Door	Door, wd sc type	nw	25.41	4.67	0	0	0	0	0	0	0	0	
Wall	15B15-0wc-4	nw	4.39	0.00	0	0	0	0	120	527	0	0	
Ceil	16B-50ad	-	1.54	0.75	85	131	64	0	0	0	0	0	
Flor	21A-32t	-	1.54	0.00	0	0	0	0	1980	3049	0	0	
12 Infiltration	Heating Load (Btuh)		Effect ACH		WAR 0	0			WAR 0	0			
	Sensible Load (Btuh)		0.15				0					0	
	Latent Load (Btuh)												
13 Internal	a Occupants at 230 and 200 Btuh				0		0	0	0		0	0	
	b Scenario number						0				0		
	c Default Adjustments												
	d Custom Appliances						0	0			0	0	
	e Plants							0				0	
14 Subtotals	Sum lines 6 through 12					0	0			6420	0		
15 Duct Loads	EHLF & ESGF		0	0		0	0			0	0		
	ELG							0				0	
16 Ventilation Loads	Vent Cfm	75	E Cfm	75									
17 Winter Humidification Load	Gal/Day			0									
18 Piping Load													
19 Blower Heat													
20 AED Excursion & Latent Moisture Migration Load							-2				0		
21 Total Load	Sum lines 13 through 19					0	0			6420	0		

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Duct System Summary

Entire House

AMS Of Indiana, Inc.

Job: KBM-3266 S3 3005-TARC...
Date: 3/6/24
By: AMS of Indiana, Inc.

3933 East Jackson Blvd., Elkhart, IN 46516

Project Information

For: CHAMPION HOME BUILDERS, KBM-3266 S3 3005-TARCZALI

	Heating	Cooling
External static pressure	0.50 in H ₂ O	0.50 in H ₂ O
Pressure losses	0.16 in H ₂ O	0.16 in H ₂ O
Available static pressure	0.34 in H ₂ O	0.34 in H ₂ O
Supply / return available pressure	0.242 / 0.098 in H ₂ O	0.242 / 0.098 in H ₂ O
Lowest friction rate	0.066 in/100ft	0.066 in/100ft
Actual air flow	644 cfm	644 cfm
Total effective length (TEL)	514 ft	

Supply Branch Detail Table

Name	Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
B1	c 754	38	46	0.132	6.0	0x0	VIFx	23.5	160.0	st1
B1-A	c 754	38	46	0.142	6.0	0x0	VIFx	30.8	140.0	st1
B2	c 914	31	55	0.079	6.0	0x0	VIFx	55.0	250.0	st4
B3	c 922	31	56	0.078	6.0	0x0	VIFx	66.5	245.0	st4
BA1	h 2285	53	45	0.080	6.0	0x0	VIFx	40.8	260.0	st4
BA2	h 506	12	4	0.135	6.0	0x0	VIFx	3.5	175.0	st1
BA3	c 39	2	2	0.084	6.0	0x0	VIFx	73.0	215.0	st4
C1	h 483	11	4	0.133	6.0	0x0	VIFx	17.3	165.0	st1
CRWL	h 2140	50	0	0.142	6.0	0x0	VIFx	20.0	150.0	st1
CRWL-A	h 2140	50	0	0.134	6.0	0x0	VIFx	30.0	150.0	st2
CRWL-B	h 2140	50	0	0.080	6.0	0x0	VIFx	65.3	235.0	st4
DRKTLR	c 1418	56	86	0.136	6.0	0x0	VIFx	38.3	140.0	st2
DRKTLR-A	c 1418	56	86	0.085	6.0	0x0	VIFx	68.8	215.0	st8
DRKTLR-B	c 1418	56	86	0.133	6.0	0x0	VIFx	21.5	160.0	st2
DRKTLR-C	c 1418	56	86	0.085	6.0	0x0	VIFx	59.0	225.0	st8
ENTRY	c 541	28	33	0.066	6.0	0x0	VIFx	75.1	290.0	st4
U	h 1137	26	10	0.138	6.0	0x0	VIFx	9.8	165.0	st2



Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Duct Material	Trunk
st4	Peak AVF	195	191	0.066	351	8.6	16 x 5	RectFbg	st1
st2	Peak AVF	301	354	0.085	447	10.2	19 x 6	RectFbg	
st1	Peak AVF	343	290	0.066	434	10.6	19 x 6	RectFbg	
st8	Peak AVF	112	172	0.085	387	7.8	16 x 4	RectFbg	
									st2

Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb5	0x 0	147	146	82.2	0.120	269	10.0	0x 0		VIFx	rt1
rb2	0x 0	275	344	92.4	0.106	631	10.0	0x 0		VIFx	rt2
rb3	0x 0	118	49	148.5	0.066	337	8.0	0x 0		VIFx	rt2
rb4	0x 0	105	105	117.7	0.084	302	8.0	0x 0		VIFx	rt1

Return Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Duct Material	Trunk
rt1	Peak AVF	252	251	0.084	321	12.0	0 x 0	VinIFlx	
rt2	Peak AVF	392	393	0.066	501	12.0	0 x 0	VinIFlx	

Bold/italic values have been manually overridden



Job 114693	Truss HMC80509	Truss Type HINGE MONO	Qty 1	Ply 1	Highland - 379 4653
---------------	-------------------	--------------------------	----------	----------	------------------------

UFP Industries Inc., Grand Rapids, MI 49525, Matt Salonek 8.620 e Sep 22 2022 MiTek Industries, Inc. Wed Oct 11 15:16:28 2023 Page 1 of 1

Copyright ©2023 UFP Industries, Inc. All Rights Reserved




Plate Offsets (X,Y)-- [2:0-0-0,0-0-1], [3:0-4-4,0-1-8], [4:0-0-4,0-0-0], [5:0-1-4,0-1-0], [8:0-3-4,0-2-8], [9:0-1-12,0-0-8]					
SPACING--: 2-0-0 LOADING (psf) TCLL 46.2 (Ground Snow=60.0) TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING--: 1-4-0 LOADING (psf) TCLL 69.3 (Ground Snow=90.0) TCDL 15.0 BCLL 0.0 * BCDL 15.0	SPACING--: 2-0-0 LOADING (psf) Plate Grip DOL 1.00 Lumber DOL 1.00 Rep Stress Incr YES Code IBC2021/TPI2014	CSI. TC 0.81 BC 0.87 WB 0.76 Matrix-R	DEFL. in (loc) l/defl L/d Vert(LL) -0.10 8-9 >999 240 Vert(CT) -0.20 8-9 >857 180 Horz(CT) 0.03 8 n/a n/a	PLATES GRIP MT20 197/144 MT18HS 197/144 Weight: 76 lb FT = 0%

LUMBER- TOP CHORD 2x6 SPF No.2 *Except* T3: 2x4 SPF No.2, T2: 2x6 SPF 2100F 1.8E BOT CHORD 2x6 SPF No.2 WEBS 2x3 SPF Stud *Except* W2: 2x4 SPF No.2, W4: 2x8 SPF No.2	BRACING- TOP CHORD Structural wood sheathing directly applied or 4-9-10 oc purlins, except end vertical[P] BOT CHORD Rigid ceiling directly applied or 6-5-10 oc bracing. WEBS 1 Row at midpt 3-8
---	---

REACTIONS. (lb/size) 2=1098/0-3-8 (min. 0-1-14), 7=-0/Mechanical, 8=954/Mechanical Max Horz 2=403(LC 12), 7=-82(LC 19) Max Uplift 2=-349(LC 12), 8=-458(LC 12) Max Grav 2=1212(LC 19), 8=1249(LC 19)	REACTIONS. (lb/size) 2=1098/0-3-8 (min. 0-1-14), 7=-0/Mechanical, 8=954/Mechanical Max Horz 2=403(LC 12), 7=-82(LC 19) Max Uplift 2=-479(LC 8), 8=-528(LC 8) Max Grav 2=1212(LC 19), 8=1249(LC 19)
--	--

FORCES. (lb) - Maximum Compression/Maximum Tension TOP CHORD 1-2=0/66, 2-11=-2174/677, 3-11=-2015/686, 3-4=-638/0, 4-12=-600/0, 5-12=-395/14, 5-6=-175/41, 6-7=-94/49, 8-10=-777/481 BOT CHORD 2-9=-1081/1870, 8-9=-1081/1870 WEBS 3-9=0/384, 3-8=-1616/922, 5-10=-827/512
--

REQUIRED FIELD JOINT CONNECTIONS - Maximum Compression (lb)/ Maximum Tension (lb)/ Maximum Shear (lb)/ Maximum Moment (lb-in)
6=118/47/55/0, 10=827/512/283/0

- NOTES-** (13-16)
- 1) Wind: ASCE 7-16; Vult=145mph (3-second gust) Vasd=115mph @24in o.c.; TCCL=4.0psf; BCDL=4.0psf; (Alt. 178mph @16in o.c.; TCCL=6.0psf; BCDL=6.0psf); h=30ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 14-9-12 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCCL: ASCE 7-16; Pg=60.0 psf; Ps=46.2 psf (Lum DOL=1.00; Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10)
 - 3) Roof design snow load has been reduced to account for slope.
 - 4) Unbalanced snow loads have been considered for this design.
 - 5) This truss has been designed for greater of min roof live load of 19.0 psf or 2.00 times flat roof load of 46.2 psf on overhangs non-concurrent with other loads.
 - 6) All plates are MT20 plates unless otherwise indicated.
 - 7) See HINGE PLATE DETAILS for plate placement.
 - 8) Provisions must be made to prevent lateral movement of hinged member(s) during transportation.
 - 9) All additional member connections shall be provided by others for forces as indicated.
 - 10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the chord and any other members.
 - 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 349 lb uplift at joint 2 and 458 lb uplift at joint 8.
 - 13) This truss is designed in accordance with the 2021 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
 - 14) This truss is designed in accordance with the 2018 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
 - 15) This truss is designed in accordance with the 2015 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
 - 16) Based on: HMC80508. Changes: Removed kingpost kicker.



The professional engineering seal indicates that a licensed professional engineer has designed the truss under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

10/16/2023

WARNING - Verify design parameters and READ NOTES

UFP Industries, Inc.
PHONE (616)-364-6161

2801 EAST BELTLINE RD, NE
GRAND RAPIDS, MI 49525


Truss shall not be cut or modified without approval of the truss design engineer.
This component has only been designed for the loads noted on this drawing. Construction and lifting forces have not been considered. The builder is responsible for lifting methods and system design. Builder responsibilities are defined under TPI1. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult BCSI 1-06 from the Wood Truss Council of America and Truss Plate Institute Recommendation available from WTCA, 6300 Enterprise LN, Madison, WI 53719 J:\support\MitekSupp\templates\ufp_tpe



UFP INDUSTRIES

Job	Truss	MFG	Customer
114693	HMC80509	379	HIGHLAND

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.



I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

PRINT NAME: STUART WALTER

SIGNATURE: Stuart L. Walter

DATE: 10/16/2023 LIC # 47774





Generated by REScheck-Web Software Compliance Certificate

Project 290HGKBM-3266S33005 (Tarczali) S#004959

Energy Code: **2021 IECC**
Location: **Estes Park, Colorado**
Construction Type: **Single-family**
Project Type: **New Construction**
Conditioned Floor Area: **1,980 ft2**
Glazing Area: **14%**
Climate Zone: **5 (7944 HDD)**
Permit Date:
Permit Number:

Construction Site:

Owner/Agent:

Designer/Contractor:

Compliance: Passes using UA trade-off

Compliance: **1.9% Better Than Code** Maximum UA: **264** Your UA: **259**

The % Better or Worse Than Code Index reflects how close to compliance the house is based on code trade-off rules. It DOES NOT provide an estimate of energy use or cost relative to a minimum-code home.

Slab-on-grade tradeoffs are no longer considered in the UA or performance compliance path in REScheck. Each slab-on-grade assembly in the specified climate zone must meet the minimum energy code insulation R-value and depth requirements.

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Prop. U-Factor	Req. U-Factor	Prop. UA	Req. UA
Ceiling: Flat Ceiling or Scissor Truss	1,980	50.0	0.3	0.025	0.024	50	48
Wall: Wood Frame, 16" o.c.	1,920	21.0	0.0	0.057	0.045	89	70
Door 1: Solid Door (under 50% glazing)	88			0.170	0.320	15	28
Door 2: Glass Door (over 50% glazing)	41			0.330	0.320	14	13
Window: Vinyl Frame	228			0.260	0.320	59	73
Crawl Wall: Solid Concrete or Masonry Wall height: 4.0' Depth below grade: 3.0' Insulation depth: 3.0'	768	0.0	15.0	0.056	0.055	32	32

Additional Efficiency Package(s)

Required: 1 Proposed: 1

Description	Credits
Efficient HVAC Performance	1.0

Compliance Statement: The proposed building design described here is consistent with the building plans, specifications, and other calculations submitted with the permit application. The proposed building has been designed to meet the 2021 IECC requirements in REScheck Version: REScheck-Web and to comply with the mandatory requirements listed in the REScheck Inspection Checklist.

<u>Robert A. Stone, C4D Tech Designer</u>	<u>[Signature]</u>	<u>03/14/24</u>
Name - Title	Signature	Date



2021 IECC Energy Efficiency Certificate

Insulation Rating	R-Value
-------------------	---------

Above-Grade Wall	21.00
Below-Grade Wall	15.00
Floor	0.00
Ceiling / Roof	50.00
Ductwork (unconditioned spaces):	8.00

Glass & Door Rating	U-Factor	SHGC
---------------------	----------	------

Window	0.26	
Door	0.17 & 0.33	

Heating & Cooling Equipment	Efficiency
-----------------------------	------------

Heating System: __ GAS (60)N96MSN-0601716, 95%, OUTPUT: 57,000, CARRIER__

Cooling System: __ ON SITE BY OTHERS - NO DATA AVAILABLE__

Water Heater: __ GAS (40 GAL) 24140FDVX, 93%, 1st hour, Rheem__

Name: Eddie Anstine Date: 03/14/2024

Comments

Champion Homes
1660 Rowe Avenue
PO Box 427
Worthington, MN 56187
(507) 376-9460

Colorado Division of Housing
1313 Sherman Street Room 321
Denver, CO 80203

Gas Furnace Deration Calculations

Model #: KBM-3266S33005
Home Location: Estes Park, CO
Home Elevation: 7761 feet above sea level
Furnace Deration: 4 % for each 1,000 feet over sea level
Deration Factor (DF): 0.31

Furnace Model: **N96MSN-0601716**

Furnace Deration Calculations

Input	60,000	Efficiency	95
Output	57,000		
Deration factor	0.31		
Deration loss	17,670		
Output	57,000		
Deration loss	17,670		
Derated Output	39,330		

Electrical calculation - 100 Amps or greater

Serial # 4959 Model KBM-3266S33005
 Delivery Point City Estes Park State CO
 Construction type: Residential Factor 3.00

Unit	Length		Width		Area	
	ft	in	ft	in		
A	76	0	15	0	1140	sq.ft.
B	76	0	15	0	1140	sq.ft.
C					0	sq.ft.
Total Area					2280	sq.ft.
x Construction factor					3.00	
General lighting					6840	Watts

Circuits

Qty	Items	Watts	Load calculations			
	General Lighting		6,840	=	6.84	KW
5	Small Appliance	1,500	7,500	=	7.5	KW
1	Water Heater	4,500	4,500	=	4.5	KW
1	Furnace blower	150	150	=	0.15	KW
	Elec. F.Place	1,500	0	=	0	KW
1	Range	6,400	6,400	=	6.4	KW
	Cooktop	6,400	0	=	0	KW
1	Wall Oven	7,700	7,700	=	7.7	KW
1	Dishwasher	1,400	1,400	=	1.4	KW
1	Ranghood	150	150	=	0.15	KW
3	Bath Fans	100	300	=	0.3	KW
1	Clothes Washer	1,500	1,500	=	1.5	KW
1	Dryer	5,000	5,000	=	5	KW
			Total Load		41.44	KW

Heating and Cooling Equipment

	Heat	23kW	22,000	0	=	0.00	KW
1	Cooling Equip		6,800	6,800	=	6.80	KW
Heating load factor (65%)						0.00	KW
Cooling load factor (100%)						6.80	KW

First 10 KW of total load @ 100%		10.00	KW
31.44 Remainder of total load @ 40%		12.58	KW
Heating or Cooling equipment load		6.80	KW
Total design load		29.38	KW
Minimum required amperage		122.40	Amps
(Total design load/240*1000)			

Install 200 amp, 120/240 volt, single phase, service panel

Unblocked, 7/16" Wood Roof Diaphragm


Model: 290-Tarccall

Spacing at 6 in. o.c. at diaphragm perimeter, 6 in. o.c. at other panel edges, 12 in. o.c. field

Loading Type		Wind	Code Reference	
Diaphragm Type	Unblocked		ESR-1539	
Sheathing Layout	Case 1		6 in	
Fastener Type	0.131	1/4" dia nails	6 in	
		Minimum 2" fastener length	Max L/W Ratio	3:1
Components & Cladding:		Corner	Fasten at: 6" o.c.	Panel Edges and
		Field	Fasten at: 6" o.c.	Panel Edges and

Roof Diaphragm Data :		House Layout :	
Diaphragm Capacity =	320 pif	Roof Pitch =	5.00/12
Reduction Factor =	0.92	Overhang, OH =	12 in
Max. Allowable Shear =	294 pif	Wall Height, H =	108 in
		Floor Width, W =	15.00 ft
		Number of Boxes =	2
		Length =	66.00 ft
		Porch Pitch =	5/12
		Porch Length =	10 ft.

Wind Load : ASCE7-10		Diaphragm Load (Field) =	
Wind Speed (Vult) =	175 mph	Diaphragm Load (Edge) =	222.6 pif
Exposure =	C	Porch Load =	0.9 pif
Mean Roof Height =	20.00 ft	Edge Distance, a =	3.0 ft.
Adjustment Factor =	1.29	Windward Uplift =	67.8 pif
Wall Load (Field) =	34.4 psf		
Wall Load (Edge) =	49.5 psf		
Roof Load (Field) =	0.4 psf		
Roof Load (Edge) =	0.0 psf		



Diaphragm Shear Load :

Main Roof Shear =	5,389 lbs
Porch Roof Shear =	5,398 lbs
Allowable Shear =	9,421 lbs

Diaphragm Moment Load :

Diaphragm Chord :	#3	2x6 (SPF)
Actual Moment =	86,358	lb-ft
Allowable Moment =	137,280	lb-ft

Change from Blocked to Unblocked Diaphragm Not Required

Diaphragm Capacity =	320 pif
Max. Shear for Unblocked Diaphragm =	294 pif (for SPF)
Maximum Roof Shear Wind =	5,398 lbs
Maximum Roof Shear Seismic =	0 lbs
Length from Blocked to Unblocked =	-18.01 ft. (From Roof Edge)

Blocking Not Required
PROFESSIONAL ENGINEER
STEVEN C. DAME
53094
04/02/2024
Roof Diaphragm
Copyright © 2020 by CHAMPIONHOMEBUILDERS, LLC
1-Story Diaphragms & Shearwalls (ASCE7-10).xlsx


Unblocked, 7/16" Wood Roof Diaphragm

Model: 290-Tarccall

Spacing at 6 in. o.c. at diaphragm perimeter, 6 in. o.c. at other panel edges, 12 in. o.c. field

Loading Type		Wind	Code Reference	
Diaphragm Type	Unblocked		ESR-1539	
Sheathing Layout	Case 3		6 in	
Fastener Type	0.131	1/4" dia nails	6 in	
		Minimum 2" fastener length	Max L/W Ratio	3:1
Roof Diaphragm Data :		Diaphragm Capacity =	235 pif	
		Reduction Factor =	0.92	
		Max. Shear =	216 pif	

Wind Load : ASCE7-10		House Layout :	
Wind Speed (Vult) =	175 mph	Roof Pitch =	5/12
Exposure =	C	Overhang, OH =	12 in
Mean Roof Height =	20.00 ft	Wall Height, H =	108 in
Adjustment Factor =	1.29	Floor Width, W =	15.00 ft
Wall Load (Field) =	24.9 psf	Number of floors =	2
Wall Load (Edge) =	37.6 psf	Length =	66.00 ft



Span Calculation :

Allowable Shear Load =	14,269 lbs
Maximum Span =	151.2 ft.

B.

Chord Force =	4,290 lbs
Moment due to Chord =	283,140 ft-lbs
Maximum Span =	105.9 ft.

Diaphragm Chord: #3 2x6 (SPF)

Change from Blocked to Unblocked Diaphragm Not Required

Diaphragm Capacity =	235 pif
Max. Shear for Unblocked Diaphragm =	216 pif (for SPF)
Maximum Reaction Wind =	3,105 lbs
Maximum Reaction Seismic =	0 LBS
Length from Blocked to Unblocked =	-51.66 ft. (From Roof Edge)

Blocking Not Required

Blocking Not Required
PROFESSIONAL ENGINEER
STEVEN C. DAME
53094
04/02/2024
Roof Diaphragm (Endwall)
Copyright © 2020 by CHAMPIONHOMEBUILDERS, LLC
1-Story Diaphragms & Shearwalls (ASCE7-10).xlsx

7/16" Rated Shearwall at Endwall


Model: 290-T trussail

Connected by 0.131 dia. Nails spaced @ 3 in o.c. (edges), 12 in o.c. (field)

Loading Type = Wind

Code Reference ESR-1539

Shearwall Data :		Stud Spacing		Components & Cladding	
Shearwall Capacity =	685 plf	16 in o.c.	Blocked	Corner	Edge
Reduction Factor =	0.92	for SPF	1.0	Field	Field
Max. Shear =	630 plf				



Total Shear at Endwall = 5,389 lbs
Shear Wall Required = 8.55 ft.
Available Wall = 10.42 ft.
Actual Shear Value = 517 plf.
Shear Capacity = 6.95 lbs
Anchor Capacity = 8.440 lbs
Anchor Uplift Force = 4.281 lbs

(2) Simpson (or EQ.)
MSTC400 @ 4.228'w
tension side

Shearwall to Roof Truss Connection:



(Out of Plane)
Fasteners = #8x4" Toe-Screws (NDS)
Fastener Capacity = 103.6 lbs/screw
Shear req'd @ 7.0 in. oc.
Fasteners req'd @ 7.0 in. oc.

In Plane and Out of Plane Shear Option:

Without OSB overlap (OSB seam at B/C of truss)
Shear Load = 348.0 plf
Fasteners req'd @ 3.5 in. oc.

Bottom Plate to Rim Joist Connection:

(Out of Plane)
Fasteners = 0.131 x 3.25" Nails (NDS)
Fastener Capacity = 100.2 lbs/nail
Shear Load = 172.0 plf
Nails req'd @ 6.5 in. oc.
Number per cavity = 3.0 nails



7/16" Rated Shearwall at Endwall

Model: 290-T trussail


(630 plf W/all)

Shear wall to rim joist connection: (ESR-1539)

(In Plane)

Fastener = 0.131 Nail
Fastener Capacity = 131.2 lbs/nail
Shear Load = 517.4 plf
Fasteners req'd @ 3.0 in. oc.


use (2) rows: 6.0 in. oc. staggered



Bottom Half Wall Shear Connection:

(Out of Plane)

Fastener = 0.131 x 3.25" Toe Nail (ESR-1539)
Fastener Capacity = 108.9 lbs/nail
Shear Load = 205.7 plf
Nails req'd @ 6.0 in. oc.




Shear Transfer from Rim Joist to Sill Plate:

(In Plane)

Fastener = 0.131 Nail
Fastener Capacity = 131.2 lbs/nail
Lateral Shear Load = 179.9 plf
Uplift Shear Load = 16.0 plf
Nails req'd @ 8.0 in. oc.

Option: LTP4 Clips = 36 in. o.c.




Roof Joist Connection: (NDS)

Angle = 45 deg
Angle = 0.7854 rad
Screws = 131 lbs/bolt
Shear Capacity = 204 lbs/bolt
Withdrawal Capacity = 131.5 lbs/bolt
Combined Capacity = 131.5 lbs/bolt

Roof Uplift Connection:

Uplift = 42.6 plf
Roof Trb = 195.00 in.
Moment = 4.789 lbs-ft
Tension Force = 298.9 plf
Spacing = 12 in o.c.
Lags = 17 Screws
#10 Screws = 5 in o.c.
Alternating Sides




Roof Shear Load Connection: From Diaphragm

Connect 26 Ga. Metal Strip with 15 Ga. Staples

Total Load across Joint = 180 plf
Capacity Parallel to Grain = 92 lbs/staple
Spacing = 6 in o.c.


Screw Option: (no metal strip required) (NDS)

Connect W/In = #10 x 4" Screws
Total Load across Joint = 180 plf
Capacity Parallel to Grain = 145 lbs/screw
Spacing = 9 in o.c.



Anchor Bolt Shear: (NDS)

Number of Sill Plates = 1
Fastener = 5/8 in. dia. Anchor Bolt
Shear Parallel to Grain = 1179.9 plf
Shear Perpendicular to Grain = 205.7 plf
Capacity Parallel to Grain = 1562 lbs/bolt
Capacity Perpendicular to Grain = 928 lbs/bolt
Spacing = 54 in. oc.




7/16" Rated Shearwall at Endwall

Model: 290-T arccall

Connected by: 0.131 dia. Nails spaced @ 6 in. o.c. (edges), 12 in. o.c. (field)

Loading Type = Wind Minimum Fastener Length Code Reference ESR-1539

Shearwall Data:		Stud Spacing		Components & Cladding	
Shearwall Capacity =	365 pif	16 in. o.c.	Unblocked	Corner	Edge
Reduction Factor =	0.92	for SPF	Factor	Field	Field
Max. Shear =	201 pif	0.6		6" o.c.	12" o.c.



Total Shear at Endwall = 5,389 lbs
Shear Wall Required = 26.75 ft.
Available Wall = 30.00 ft.
Actual Shear Value = 180 pif.
Shear Capacity = 6.044 lbs
Anchor Capacity = 4,220 lbs
Anchor Uplift Force = 537 lbs

(1) Simpson (or EQ.)
MSTC400 @ 4.220k
tension ea

Shearwall to Roof Truss Connection:



(Out of Plane)

Fasteners = #8x4" Toe-Screws (NDS)
Fastener Capacity = 103.6 lbs/screw
Shear Load = 168.3 pif
Fasteners req'd @ 7.0 in. o.c.
In Plane and Out of Plane Shear Option:
Without OSB overlap (OSB seam at B/C of truss)
Shear Load = 348.0 pif
Fasteners req'd @ 3.5 in. o.c.

Bottom Plate to Rim Joist Connection:

(Out of Plane)

Fasteners = 0.131 x 3.25" Nails (NDS)
Fastener Capacity = 100.2 lbs/nail
Shear Load = 172.0 pif
Nails req'd @ 6.5 in. o.c.
Number per cavity = 3.0 nails



THESE CALCULATIONS AND SPECIFICATIONS ARE ORIGINAL.
PROFESSIONAL SEAL AND SIGNATURE REQUIRED FOR ALL SETS OF
CHAMPION HOME BUILDERS, INC.
COPYRIGHT © 2020 BY CHAMPION

290-T arccall - 1-Story Diaphragms & Shearwalls (ASCE-7-10) J&S
Segmented (Endwall) (2)

7/16" Rated Shearwall at Endwall

Model: 290-T arccall

(201 pif Wall)

Shear wall to rim joist connection: (ESR-1539)

(In Plane)

Fastener = 0.131 Nail
Fastener Capacity = 131.2 lbs/nail
Shear Load = 179.6 pif
Fasteners req'd @ 8.5 in. o.c.

use (2) rows: 6.0 in. o.c. staggered

Bottom Half Wall Shear Connection:

(Out of Plane)

Fastener = 0.131 x 3.25" Toe Nail (ESR-1539)
Fastener Capacity = 108.9 lbs/nail
Shear Load = 205.7 pif
Nails req'd @ 6.0 in. o.c.

Shear Transfer from Rim Joist to Sill Plate:

(In Plane)

Fastener = 0.131 Nail
Fastener Capacity = 131.2 lbs/nail
Lateral Shear Load = 179.9 pif
Uplift Shear Load = 16.0 pif
Nails req'd @ 8.0 in. o.c.

Option: LTP4 Clips = 36 in. o.c.

Roof Joist Connection: (NDS)

Shear Capacity = 239 lbs/boit
Withdrawal Capacity = 440 lbs/boit
Combined Capacity = 309.7 lbs/boit

Roof Uplift Connection:
Uplift = 42.6 pif
Roof Trb = 195.00 in.
Moment = 4,789 lbs-ft
Tension Force = 298.9 pif

Roof Shear Load Connection: From Diaphragm

Connect 26 Ga. Metal Strip with 15 Ga. Staples




Total Load across Joint = 180 pif
Capacity Parallel to Grain = 92 lbs/staple
Spacing = 6 in. o.c.

Screw Option: (no metal strip required) (NDS)




Connect W/In = #10 x 4" Screws
Total Load across Joint = 180 pif
Capacity Parallel to Grain = 145 lbs/screw
Spacing = 9 in. o.c.

Anchor Bolt Shear: (NDS)

Number of Sill Plates = 1
Fastener = 5/8 in. dia. Anchor Bolt
Shear Parallel to Grain = 179.9 pif
Shear Perpendicular to Grain = 205.7 pif
Capacity Parallel to Grain = 1562 lbs/boit
Capacity Perpendicular to Grain = 928 lbs/boit
Spacing = 54 in. o.c.



Angle = 45 deg
Angle = 0.7854 rad
Screws = #10
Screws = 131 lbs/boit
Withdrawal Capacity = 204 lbs/boit
Combined Capacity = 131.5 lbs/boit



THESE CALCULATIONS AND SPECIFICATIONS ARE ORIGINAL.
PROFESSIONAL SEAL AND SIGNATURE REQUIRED FOR ALL SETS OF
CHAMPION HOME BUILDERS, INC.
COPYRIGHT © 2020 BY CHAMPION

290-T arccall - 1-Story Diaphragms & Shearwalls (ASCE-7-10) J&S
Segmented (Endwall) (2)

3/11/2024



Z/16 in. Thick Rated Shear Wall

Model: **290-Tarczall Sidewall 1**

Connected by: **15** ga. Staples @ **6** in. o.c. (edge), 12 in. o.c. (field)

Loading Type = **Wind**

Loading Factor = **1.4**

Shearwall Data:

Shearwall Capacity = **259** pif
Reduction Factor = **0.82** for SPF
Maximum Shear = **127** pif (for SPF)

ESR-1539

Stud Spacing

16	In. o.c.
Unblocked	Horz. Seams
0.6	Factor

Components & Cladding

Corner	Edge	Field
6" o.c.	6" o.c.	8" o.c.
6" o.c.	6" o.c.	9" o.c.

Wall Height, H = **108** in

Wall Segment Lengths

ft	in	ft	h/b	% Capacity	Strength (pif)
10	9	10.75	0.84	100%	127
5	2	5.17	1.74	100%	127
11	1	11.08	0.81	100%	127
12	7	12.58	0.72	100%	127
0.00		0.00	0.00	0%	127
0.00		0.00	0.00	0%	127
0.00		0.00	0.00	0%	127
39.58		0.00	0.00	0%	127

Total Shear @ Wall = **3,105** lbs
Actual Shear Wall Segment Lengths = **39.58** ft.

Perforated Shear Wall Length = **66.00** ft.

Actual Shear Value = **102.8** pif.

Percent Full Height Sheathing

Lower Bound = **0.60**
Upper Bound = **0.60**

Maximum Opening Height

64	In
0.59	
0.50	
0.67	


Interpolation

0.8	0.67
0.83	0.71

0.73	
0.76	

	1/3 h	1/2 h	2/3 h	5/6 h	1 h
10%	1.00	0.69	0.53	0.43	0.36
20%	1.00	0.71	0.56	0.45	0.38
30%	1.00	0.74	0.59	0.49	0.42
40%	1.00	0.77	0.63	0.53	0.46
50%	1.00	0.80	0.67	0.57	0.50
60%	1.00	0.83	0.71	0.63	0.56
70%	1.00	0.87	0.77	0.69	0.63
80%	1.00	0.91	0.83	0.77	0.71
90%	1.00	0.95	0.91	0.87	0.83
100%	1.00	1.00	1.00	1.00	1.00

Co = **0.76**
Perforated Capacity = **97** pif
Allowable Shear Force = **3850** lbs
Anchor Uplift Force = **0** lbs



THESE CALCULATIONS ARE THE PROPERTY OF CHAMPION HOME BUILDERS, INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. CHAMPION HOME BUILDERS, INC. PROPRIETARY AND CONFIDENTIAL MATERIALS OF CHAMPION HOME BUILDERS, INC. Copyright © 2020 BY CHAMPION290-Tarczall-1-Story Diaphragms & Shearwalls (ASCE)-10.xls

Perforated (Sidewall)

3/11/2024




Z/16 in. Thick Rated Shear Wall

Model: **290-Tarczall Sidewall 1**


Roof Truss to Top Plate Connection:

Fasteners = **0.131 x 3.25" Toe Nails (NDS)**
Fastener Capacity = **108.9** lbs/nail
Parallel Shear Load = **47.0** pif
Perpendicular Shear Load = **117.4** pif
No. of nails req'd = **2** per truss




Bottom Plate to Rim Joist Connection:

Fasteners = **0.131 x 3.25" Nails (NDS)**
Fastener Capacity = **100.2** lbs/nail
Shear Load = **137.2** pif
Nails req'd @ **8.5** in. oc.
Nails req'd @ **3** per stud cavity



Bottom Half Wall Shear Connection:

(Out of Plane)
Fastener = **0.131 x 3.25" Toe Nail (ESR-1539)**
Fastener Capacity = **108.9** lbs/nail
Shear Load = **143.5** pif
Nails req'd @ **9.0** in. oc.




Shear Transfer from Rim Joist to Sill Plate:

Fastener = **15** Staple
Fastener Capacity = **72** lbs/each
Lateral Shear Load = **47.0** pif
Uplift Shear Load = **67.8** pif
Nails req'd @ **10.0** in. oc.
Option: LTP4 Clips = **78.0** in. o.c.

ESR-1539


Minimum 1/75' fastener length



Anchor Bolt Shear and Uplift:

of Sill Plates = **1**
Fastener = **5/8** in. dia. Anchor Bolt

Shear Parallel to Grain = **47.0** pif
Shear Perpendicular to Grain = **143.5** pif
Capacity Parallel to Grain = **1552** lbs/bolt
Capacity Perpendicular to Grain = **928** lbs/bolt
Required Shear Spacing = **72** in. oc.
Uplift = **67.8** pif
Washer Area = **2.03** in²
Cb = **1.21**
Fcp = **425** psi
Anchor Bolt Uplift Capacity = **1050** lbs/bolt
Required Uplift Spacing = **180** in. oc.



THESE CALCULATIONS ARE THE PROPERTY OF CHAMPION HOME BUILDERS, INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. CHAMPION HOME BUILDERS, INC. PROPRIETARY AND CONFIDENTIAL MATERIALS OF CHAMPION HOME BUILDERS, INC. Copyright © 2020 BY CHAMPION290-Tarczall-1-Story Diaphragms & Shearwalls (ASCE)-10.xls

Perforated (Sidewall)

3/11/2024



Z/16 in. Thick Rated Shear Wall

Model:

290-Tarczall
Sidewall 2

Connected by: **15** ga. Staples @ **4** in. o.c. (edge), 12 in. o.c. (field)

Loading Type = **Wind**
Minimum 1.75" fastener length

Loading Factor = **1.4**

Shearwall Data:

Shearwall Capacity = **392** pif
Reduction Factor = **0.82** for SPF
Maximum Shear = **193** pif (for SPF)

ESR-1539

Components & Cladding

Corner Field	Edge		Field	
	4" o.c.	8" o.c.	4" o.c.	9" o.c.

Wall Height, H = **108** in

Wall Segment Lengths		ft		h/b		% Capacity		Strength (pif)	
1	4	ft	in	2.20	100%	193		193	
2	7	7.17		1.26	100%	193		193	
3	4	4.17		2.16	100%	193		193	
4	4	4.83		1.86	100%	193		193	
5	2	2.75		3.27	100%	193		193	
6	3	3.42		2.63	100%	193		193	
7	3	3.42		2.63	100%	193		193	
8		0.00		0.00	0%	193		193	
		29.83							

Total Shear @ Wall = **3,105** lbs
Actual Shear Wall Segment Lengths = **29.83** ft.

Perforated Shear Wall Length = **60.17** ft.

Actual Shear Value = **166.8** pif.

Percent Full Height Sheathing

Lower Bound = **0.50**
Upper Bound = **0.50**

Maximum Opening Height

Lower Bound = **0.74** in
Upper Bound = **0.83** in


Interpolation

0.63	0.53
0.67	0.57

0.59	0.63
------	------

	1/3 h	1/2 h	2/3 h	5/6 h	1 h
10%	1.00	0.69	0.53	0.43	0.36
20%	1.00	0.71	0.56	0.45	0.38
30%	1.00	0.74	0.59	0.49	0.42
40%	1.00	0.77	0.63	0.53	0.45
50%	1.00	0.80	0.67	0.57	0.50
60%	1.00	0.83	0.71	0.63	0.56
70%	1.00	0.87	0.77	0.69	0.63
80%	1.00	0.91	0.83	0.77	0.71
90%	1.00	0.95	0.91	0.87	0.83
100%	1.00	1.00	1.00	1.00	1.00

Co = **0.62** pif
Perforated Capacity = **120** pif
Allowable Shear Force = **3590** lbs
Anchor Uplift Force = **0** lbs



PROFESSIONAL ENGINEER
STEVEN C. DAME
53094
04/02/2024

Perforated (Sidewall) (2)
CHAMPION HOME BUILDERS, INC.
Copyright © 2020 by CHAMPION290-Tarczall-1-Story Diaphragms & Shearwalls (ASCE7-10) xlsx

3/11/2024




Z/16 in. Thick Rated Shear Wall

Model:

290-Tarczall
Sidewall 2


Roof Truss to Top Plate Connection:

Fasteners = **0.131 x 3.25" Toe Nails (NDS)**
Fastener Capacity = **108.9** lbs/nail
Parallel Shear Load = **47.0** pif
Perpendicular Shear Load = **117.4** pif
No. of nails req'd = **2** per truss




Bottom Plate to Rim Joist Connection:

Fasteners = **0.131 x 3.25" Nails (NDS)**
Fastener Capacity = **100.2** lbs/nail
Shear Load = **137.2** pif
Nails req'd @ **8.5** in. oc.
Nails req'd @ **3** per stud cavity




Bottom Half Wall Shear Connection:

(Out of Plane)
Fastener = **0.131 x 3.25" Toe Nail (ESR-1539)**
Fastener Capacity = **108.9** lbs/nail
Shear Load = **143.5** pif
Nails req'd @ **9.0** in. oc.




Shear Transfer from Rim Joist to Sill Plate:

Fastener = **15** Staple
Fastener Capacity = **72** lbs/each
Lateral Shear Load = **47.0** pif
Uplift Shear Load = **67.8** pif
Nails req'd @ **10.0** in. oc.
Option: LTP4 Clips = **78.0** in. o.c.
ESR-1539
Minimum 1.75" fastener length



Anchor Bolt Shear and Uplift:

of Sill Plates = **1**
Fastener = **5/8** in. dia. Anchor Bolt
Shear Parallel to Grain = **47.0** pif
Shear Perpendicular to Grain = **143.5** pif
Capacity Parallel to Grain = **1552** lbs/bolt
Capacity Perpendicular to Grain = **928** lbs/bolt
Required Shear Spacing = **72** in. oc.
Uplift = **67.8** pif
Washer Area = **2.03** in²
Cb = **1.21**
Fcp = **425** psi
Anchor Bolt Uplift Capacity = **1050** lbs/bolt
Required Uplift Spacing = **180** in. oc.



PROFESSIONAL ENGINEER
STEVEN C. DAME
53094
04/02/2024

Perforated (Sidewall) (2)
CHAMPION HOME BUILDERS, INC.
Copyright © 2020 by CHAMPION290-Tarczall-1-Story Diaphragms & Shearwalls (ASCE7-10) xlsx

OUT OF PLANE WIND FASTENING CALCULATIONS

Sheathing Thickness = 7/16"

Truss Spacing = 16" o.c.

Exposure Category = C

Mean Roof Height = 20 ft.

Roof Pitch = 5 : 12

Wall Stud Spacing = 16" o.c.

Exposure Factor = 1.29

Requires 3x framing at adjoining panel edges

Withdrawal Capacities:

7/16"x1.75"x14 GA Staple = 52.5 lbs

7/16"x1.75"x15 GA Staple = 48.3 lbs

7/16"x1.5"x16 GA Staple = 34.0 lbs

0.113x2" Nails = 45.0 lbs

0.120x2" Nails = 47.5 lbs

0.131 x 2.5" Nail = 69.3 lbs

0.148 x 3" Nail = 94.3 lbs

Zone 2 (Roof) Fastener Spacing			
Wind (mph)	Load (psf)	14	15
175	67.9	6.5	6.0
Zone 3 (Roof) Fastener Spacing			
Wind (mph)	Load (psf)	14	15
175	100.5	4.5	4.0
Zone 4 (Wall) Fastener Spacing			
Wind (mph)	Load (psf)	14	15
175	46.3	10.0	9.0
Zone 5 (Wall) Fastener Spacing			
Wind (mph)	Load (psf)	14	15
175	57.1	8.0	8.0



Ridgebeam Check Based of Truss Reaction

Design Loads :	Ground Snow Load =	30.0	psf	Truss#:	HMC80509	Node:	1
	Truss Reaction (Max. Grav) =	1249.0	lbs	Linear Load =	52.0	plf	Ridgebeam = Yes
	Truss Reaction (Max. Uplift) =	458.0	lbs	Uplift Load =	19.1	plf	
	Spacing =	24	" o.c.				

Species : **LVL** Grade : **2.0E** Number of Ply(s), N : **1**

LVL Properties :

Thickness, b =	1.5	in.
Fb =	2,900	psi
Fv =	280	psi
E =	2,000,000	psi

Adjustment Factors :

1. Load Duration Factor (Wind)	Cd =	1.60
1b. Load Duration Factor (Snow)	Cds =	1.00
2. Repetitive Member Factor	Cr =	1.00
3. Allowable Deflection	L /	240


Depth	Area	Sx	Ix	Cf	Fb' (Snow)	Fb' (Wind)	Fv' (Snow)	Fv' (Wind)
5.5	8.25	7.56	20.80	1.15	3337	5340	280	448
7.25	10.88	13.14	47.63	1.09	3175	5081	280	448
9.25	13.88	21.39	98.93	1.05	3039	4863	280	448
11.25	16.88	31.64	177.98	1.01	2934	4694	280	448
11.875	17.81	35.25	209.32	1.00	2905	4649	280	448
14	21.00	49.00	343.00	0.97	2821	4513	280	448
16	24.00	64.00	512.00	0.95	2754	4406	280	448
18	27.00	81.00	729.00	0.93	2696	4313	280	448
20	30.00	100.00	1000.00	0.91	2645	4232	280	448
22	33.00	121.00	1331.00	0.90	2600	4160	280	448
24	36.00	144.00	1728.00	0.88	2560	4096	280	448

Maximum Span Based on :

Depth	Moment		Shear		Deflection		Max. Span	Uplift Load (lbs)	Uplift Straps ¹	Bearing Columns ²
	Snow	Wind	Snow	Wind	Snow	Wind				
5.5	62.29	130.11	59.18	258.24	63	89	59	563	2	2
7.25	80.09	167.29	78.01	340.40	84	117	78	745	2	3
9.25	99.97	208.82	99.54	434.31	107	149	99	945	2	3
11.25	119.46	249.53	121.06	528.21	130	181	119	1136	3	4
11.875	125.48	262.11	127.78	557.55	137	191	125	1193	3	4
14	145.76	304.47	150.65	657.33	162	226	145	1384	3	4
16	164.59	343.81	172.17	751.23	185	258	164	1565	3	5
18	183.22	382.71	193.69	845.14	208	290	183	1747	4	5
20	201.65	421.22	215.21	939.04	231	322	201	1918	4	6
22	219.92	459.39	236.73	1032.94	254	355	219	2090	4	6
24	238.04	497.24	258.25	1126.85	277	387	238	2271	5	7

Notes:

- Uplift straps are 26GA by 1.25" in width and attached to beam and column stud w/ (8) 15 ga staples. (16 Total Staples)
- Bearing Column ply based of 425psi value for SPF top plate.



Header Check Based of Truss Reaction

Truss#: **HMC80509**Node: **1**

Design Loads :

Truss Reaction (Max. Grav) = **1249.0** lbs*Linear Load = **26.0** plfRidgebeam = **No**Truss Reaction (Max. Uplift) = **458.0** lbs*Uplift Load = **9.5** plfSpacing = **24** " o.c.Number of Ply(s), N : **3**

*Max. of all Trusses.

Species : **SPF / SYP**Grade : **#2**

LVL Properties :

Thickness, b = **1.5** in.Fb = **See Chart** psiFv = **135** psiE = **1,400,000** psi

Adjustment Factors :

1. Load Duration Factor (Wind)

Cd = **1.60**

1b. Load Duration Factor (Snow)

Cds = **1.00**

2. Repetitive Member Factor

Cr = **1.15**

3. Allowable Deflection

L / **240**

	Depth	Area	Sx	Ix	Cf	Fb' (Snow)	Fb' (Wind)	Fv' (Snow)	Fv' (Wind)
Triple Ply	3.50	15.75	9.19	16.08	1.00	1265	2024	135	216
	5.50	24.75	22.69	62.39	1.00	1150	1840	135	216
	7.25	32.63	39.42	142.90	1.00	1064	1702	135	216
	9.25	41.63	64.17	296.79	1.00	800	1472	135	216
	11.25	50.63	94.92	533.94	1.00	750	1380	135	216

Maximum Span Based on :

	Depth	Moment		Shear		Deflection		Max. Span	Uplift Straps ¹	Bearing Columns ²
		Snow	Wind	Snow	Wind	Snow	Wind			
Triple Ply	3.50	59.78	124.86	108.95	475.39	65	80	59	1	1
	5.50	89.56	187.08	171.21	747.04	102	125	89	1	1
	7.25	113.55	237.18	225.68	984.73	135	165	113	2	1
	9.25	125.63	281.42	287.94	1256.38	172	210	125	2	1
	11.25	147.94	331.40	350.20	1528.03	209	256	147	2	1

Notes:

1. Uplift straps are 26GA by 1.25" in width and attached to beam and column stud w/ (8) 15 ga staples. (16 Total Staples)
2. Bearing Column ply based of 425psi value for SPF top plate.

